

**DO NOT SCALE**

**IF IN DOUBT, ASK!**

REVISIONS			
REV.	DESCRIPTION	DATE	DRAWN
1	FIRST ISSUE	14/07/14	CC
2	NOTES	28/10/2014	CC
3	NOTES	27/11/2014	CC

Notes:

- The sizing and detail of the load-bearing supports must be specified and signed off by the Structural Engineer for the project.
- A400 supplied pre-assembled with 4 no. mounting brackets.
- Fire/smoke damper optional (by others).
- If mixed air delivery grille is <2.7m from above finished floor level (if installed in a suspended ceiling), finger guard grilles must be used.
- Passive and Mechanical side must be separated - see diagram A.
- Dimension A - for installation purposes, ensure sufficient gap between object (i.e. side wall) and A500 unit.

TOLERANCES EXCEPT WHERE OTHERWISE STATED

X	±	0.5MM
X.XX	±	0.05MM
ANGLES	±	0.5°

SURFACE TEXTURE TO BE 1.6 UMRA OR BETTER

DE-BURR ALL SHARP EDGES AND HOLES. ITEM MUST BE FREE FROM SCRATCHES, DENTS AND OTHER BLEMISHES.

DIMENSIONS IN MILLIMETRES



15 STURTON STREET, CAMBRIDGE, CB1 2SN  
 T: 01223 450060 F: 01223 450061  
 WWW.BREATHINGBUILDINGS.COM

TITLE:  
A400 INSTALLATION GA

DRAWING NO:  
1306\_9002\_03

MATERIAL:

FINISH:

REV	DRAWN	DATE	CHK'D	DATE
3	CC	27/11/2014		

SCALE 1:50 A3 SHEET 1 OF 1

